



# Structural Building Technologies

By Casa Di Coble





---

## **1. Precast Concrete Wall Panels & Hollow core Floor Systems**

---

---

# Background

- Precast concrete wall panels are made off site in a controlled production facility with 6000 psi concrete and steel rebar.
  - Typical lead times of wall panels are approximately 30-60 days.
  - Wall panels are typically 6 inches thick and various heights.
  - Wall panels are shipped into the Bahamas on 40 foot flat racks.
  - Wall panels are erected on site with a crane, then bolted to the slab and to each other. Some connections may also be welded together.
  - Wall panels are hurricane rated.
  - Hollow core floor systems are made off site in a controlled production facility.
  - Hollow core floors are lightweight, efficient, and strong.
  - Hollow core floors are typically 4 inches thick and varying lengths.
  - Hollow core floors are shipped into the Bahamas on 40 foot flat racks.
  - Hollow core floors are installed on site with a crane, placed on angle iron welded to the wall panels, then a 2" concrete topping is poured on top of them after installation.
-











---

# Benefits of Precast Concrete Panels

- Clean, fast and efficient building technology.
  - Stronger and more durable than traditional methods.
  - Fire resistant.
  - Termite resistant.
  - Hurricane rated.
  - Watertight and energy efficient
  - Reduced noise
  - Can take advantage of the duty free clause in Bakers Bay and import panels without having to pay duty taxes on them.
  -
-



---

# Disadvantages of Precast Concrete Panels

- Not all architecture will lend itself to this type of building methodology.
- Cost can be higher.
- Transportation can be an issue.





---

## **2. Cast In Place Concrete**

---



---

# Background

- Cast in place (C.I.P) concrete structures are built from pouring concrete on site into pre built aluminum and plywood form configurations with steel rebar embedded inside the forms.
  - The aluminum and plywood forms are built on site and reusable for multiple concrete pours.
  - The forms are 100% customizable so any architectural structure can be built with C.I.P. technology.
  - The concrete is usually poured using a crane and a 3 yard concrete bucket.
  - Once the concrete is poured a special concrete vibrator is used to make sure no voids are left in the forms.
  - Once the concrete is cured for 12 hours, the forms can be removed and the process is repeated.
  -
-











---

# Benefits of C.I.P.

- Fully customizable to support any architectural design.
  - Can be fast and efficient with the right crew.
  - Because C.I.P. is one monolithic structure, it dramatically increases the strength of the building.
  - Hurricane rated.
  - Forms can be reused reducing overall cost.
- 
-



---

# Disadvantages of C.I.P. systems

- Need a steady supply of concrete, can be an issue in Baker's Bay.
- Labor intensive.
- Time intensive.





---

### **3. CMU Block and Tie-beam Construction.**

---



---

# Background

- Traditional CMU construction is found throughout the Bahamas and is the most common form of building technology.
  - Standardized 8"x8"x16" concrete masonry unit (CMU) blocks are stacked on top of each other with cement joints. The blocks are hollow with two holes in each block
  - Steel rebar is placed at varying widths and heights inside the block holes for strength.
  - Precast or CIP headers are built above window and door openings.
  - CIP concrete tie beams and columns are built into the design for strength.
  - Typical floors are either wood framed or poured with concrete using wood or metal forms.
  -
-











---

# Benefits of CMU construction

- Cost effective
  - Can build most architectural designs.
  - Labor is easier to find.
  - Widely accepted technology.
-



---

# Disadvantages of CMU construction

- Slow and messy.
- Not as strong or accurate as pre cast or C.I.P.